



RIG 29 INVENTORY

1000 Horsepower SCR Rig w/ Top Drive

HOISTING & ROTATING EQUIPMENT

Drawworks	National 80UE with (2) GE 752
Auxiliary Brake	Wichita KKB236 w/ National Heat Exchanger
Top Drive	Varco TDS 10SA (250 ton)
Rotary Table	Continental Emsco 27 1/2"
Traveling Block	NPMP YC 225 250 ton
Hook	N/A
Swivel	N/A
Hyd. Winch	12,000#
Air Hoist	(1) Thern TA 2.5 - 16

MAST, SUBSTRUCTURE, AND POWER PACKAGE

Mast	DSI 142' x 20' 650k SHL
Substructure	DSI swing-up 400,000# set-back
Depth	16,000 feet
Horsepower	1,000 hp
Generators	(3) DSG 86 L1-6 600 volt 1100 kw each
Generator Power	(3) Cummins KTA 50 1470 hp @ 1200 rpm
SCR House	Omron IDM 4 SCR Bay x 3 Gen 1600 AMP

MUD SYSTEM EQUIPMENT

Mud Pumps	(2) Continental Emsco F-1300 1300 hp (2) GE 752 HY Torque
Pits	(2) 420 bbl each w/ 100 premix w/ (6) 5x6 cent.
Shale Shaker	(2) Derrick FLC 504
Desilter	(10) 5" Cones
Mud Agitators	(5) 15 hp
Trip Tank	110 bbls
Mud House	10' x 28' x 25' w/ low pressure hopper

PIPE HANDLING EQUIPMENT

Iron Roughneck	Hawkjaw Sr. 3 1/2" to 9" w/ 100,000# torque
Tongs	HT65
Catwalk	45' x 7' x 18" w/ 5' steel deck
Hyd. Slips	National/Varco Hydraulic
Pipe Racks	(5) sets of 30' x 18" triangular

BOP EQUIPMENT

Double	(1) 11" x 5,000# 4 1/2" pipe & blind
Annular	(1) 11" x 5,000#
Accumulator	5 Station - 120 gal. w/ remote
Choke Manifold	4" x 3" Double 5,000# w/ mud/gas separator

TUBULARS

Drill Pipe	15,000' - 4 1/2" S - 16.60#
Drill Collars	(3) 8" (21) 6 1/2"
Heavy Drill Pipe	(6) 4 1/2"

STORAGE AND OTHER EQUIPMENT

Dog House	10' x 8' x 40'
Water tank	10' x 8' x 40' w/ 2x3 cent. w/ 500 bbl
Fuel Tank	18,000 gal. w/ (2) electric transfer pumps
Parts House	10' x 8' x 40' w/ (2) 30 hp screw air comp.
HPU	GFP (2) 70 gpm p/b (1) 100 hp elect.
Wireline Unit	(1) John Deere diesel Oilworks 15,000'
Skytrack	12,000# w/ out riggers

