



# RIG 35 INVENTORY

## 1000 Horsepower AC w/ Top Drive

HOISTING & ROTATING EQUIPMENT	
<b>Drawworks</b>	RG JC40 with (1) Hitachi 1240 hp AC
<b>Auxiliary Brake</b>	Regenerative w/ Disc Park
<b>Top Drive</b>	NOV - TDS 10 (250 ton)
<b>Rotary Table</b>	RG - 27 1/2" w/ 500 hp AC drive
<b>Traveling Block</b>	RG 400 ton w/ (6) 1 1/4" sheaves
<b>Hook</b>	N/A
<b>Swivel</b>	N/A
<b>Hyd. Winch</b>	12,000#
<b>Air Hoist</b>	(1) H5UL

MAST, SUBSTRUCTURE, AND POWER PACKAGE	
<b>Mast</b>	DSI 142' x 20' 650k SHL
<b>Substructure</b>	DSI hydraulic swing-up 400,000# set-back
<b>Depth</b>	15,000 feet
<b>Horsepower</b>	1,000 hp
<b>Generators</b>	(2) DSG 86 600 volt 1571 kVA 1100 kw
<b>Generator Power</b>	(2) Cummins KTA 50 1470 hp @ 1200 rpm
<b>VFD House</b>	Omron IDM 4 VFD

MUD SYSTEM EQUIPMENT	
<b>Mud Pumps</b>	(2) RS F-1300 1300 hp (2) Hitachi 1240 hp AC
<b>Pits</b>	(2) 420 bbl each w/ 100 premix w/ (5) 5x6 cent.
<b>Shale Shaker</b>	(2) Swaco Mongoose
<b>Desilter</b>	(12) 4" Cones
<b>Mud Agitators</b>	(5) 15 hp
<b>Trip Tank</b>	110 bbls
<b>Mud House</b>	10' x 28' w/ low pressure hopper

PIPE HANDLING EQUIPMENT	
<b>Iron Roughneck</b>	Hawkjaw Sr. 3 1/2" to 9" w/ 100,000# torque
<b>Tongs</b>	DB
<b>Catwalk</b>	45' x 7' x 18" w/ 5' steel deck
<b>Hyd. Slips</b>	National/Varco Hydraulic
<b>Pipe Racks</b>	(5) sets of 30' x 18" triangular

BOP EQUIPMENT	
<b>Single</b>	(2) 13 5/8" x 5,000# 4 1/2" pipe & blind
<b>Annular Accumulator</b>	(1) 13 5/8" x 5000# 5 Station - 120 gal. w/ (2) air and triplex
<b>Choke Manifold</b>	4" x 3" Double 5,000# w/ mud/gas separator

TUBULARS	
<b>Drill Pipe</b>	14,000 - 4 1/2" S-135 - 16-60# PC & HB
<b>Drill Collars</b>	(12) 6 1/2" x 2 1/4" w/ slip recess (3) 8" x 2,500 w/ slip recess
<b>Heavy Drill Pipe</b>	(30) 4 1/2" Drillco

STORAGE AND OTHER EQUIPMENT	
<b>Dog House</b>	10' x 8' x 40'
<b>Water tank</b>	10' x 8' x 40' w/ 2x3 cent. w/ 500 bbl
<b>Fuel Tank</b>	18,000 gal. w/ (2) electric transfer pumps
<b>Parts House</b>	10' x 8' x 40' w/ (2) 30 hp screw air comp.
<b>HPU</b>	GFP (2) 70 gpm p/b (1) 100 hp elect. (1) 115 hp diesel
<b>Wireline Unit</b>	Oilworks 15,000'
<b>Skytrack</b>	12,000# w/ out riggers

