



RIG 36 INVENTORY

1000 Horsepower AC w/ Top Drive

HOISTING & ROTATING EQUIPMENT	
Drawworks	RG JC40 with (1) Hitachi 1240 hp AC
Auxiliary Brake	Regenerative w/ Disc Park
Top Drive	NOV - TDS 11 (500 ton)
Rotary Table	RG - 27 1/2" w/ 500 hp AC drive
Traveling Block	RG 400 ton w/ (6) 1 1/4" sheaves
Hook	N/A
Swivel	N/A
Hyd. Winch	12,000#
Air Hoist	(1) H5UL

MAST, SUBSTRUCTURE, AND POWER PACKAGE	
Mast	DSI 142' x 20' 650k SHL
Substructure	DSI hydraulic swing-up 400,000# set-back
Depth	15,000 feet
Horsepower	1,000 hp
Generators	(3) DSG 86 600 volt 1571 kVA 1100 kw
Generator Power	(3) Cummins KTA 50 1470 hp @ 1200 rpm
VFD House	Omron IDM 4 VFD

MUD SYSTEM EQUIPMENT	
Mud Pumps	(2) RS F-1300 1300 hp (2) Hitachi 1240 hp AC
Pits	(2) 420 bbl each w/ 100 premix w/ (5) 5x6 cent.
Shale Shaker	(2) Swaco Mongoose
Desilter	(12) 4" Cones
Mud Agitators	(5) 15 hp
Trip Tank	110 bbls
Mud House	10' x 28' w/ low pressure hopper

PIPE HANDLING EQUIPMENT	
Iron Roughneck	Hawkjaw Sr. 3 1/2" to 9" w/ 100,000# torque
Tongs	DB
Catwalk	45' x 7' x 18" w/ 5' steel deck
Hyd. Slips	National/Varco Hydraulic
Pipe Racks	(5) sets of 30' x 18" triangular

BOP EQUIPMENT	
Single	(2) 13 5/8" x 5,000# 4 1/2" pipe & blind
Annular	(1) 13 5/8" x 5000#
Accumulator	5 Station - 120 gal. w/ (2) air and triplex
Choke Manifold	4" x 3" Double 5,000# w/ mud/gas separator

TUBULARS	
Drill Pipe	14,000 - 4 1/2" S-135 - 16-60# PC & HB
Drill Collars	(12) 6 1/2" x 2 1/4" w/ slip recess (3) 8" x 2,500 w/ slip recess
Heavy Drill Pipe	(30) 4 1/2" Drillco

STORAGE AND OTHER EQUIPMENT	
Dog House	10' x 8' x 40'
Water tank	10' x 8' x 40' w/ 2x3 cent. w/ 500 bbl
Fuel Tank	18,000 gal. w/ (2) electric transfer pumps
Parts House	10' x 8' x 40' w/ (2) 30 hp screw air comp.
HPU	GFP (2) 70 gpm p/b (1) 100 hp elect. (1) 115 hp diesel
Wireline Unit	Oilworks 15,000'
Skytrack	12,000# w/ out riggers

